Request for proposals

For Milling and Asphalt

Sealed bids will be accepted by the City of Savannah, Missouri, at the City Hall, 402 Court, Savannah, MO 64485 until 10:00 a.m. on the 2nd day of April, 2015, and will be publicly opened and read aloud. Bid results will be tabulated and discussed at the following City Council meeting on the 6th day of April, 2015. Any bid received after the closing time will be returned unopened.

The City desires bids for approximately 2,234 tons of asphalt and 6,200 square yards milling. For more information, contact Kenny Lance, Director of Public Works at 816-324-7528 or 816-261-2104.

The City Council reserves the right to reject any and all proposals and waive any and all formalities. The City Council will accept the bid, which it deems to be in the best interest, and will not necessarily be bound to accept the lowest bid.

Beth Kar

Beth Kar, City Clerk

Specifications

GENERAL: To provide all labor, materials, equipment and permits to install and improve the specified streets in accordance with the specifications contained herein. *State of Missouri Prevailing Wage rates apply to the project.*

COMPLETION: Job shall be completed within Sixty (60) calendar days from the Notice to Proceed issued by the City.

BONDING & INSURANCE: Contractor shall provide a Performance & Payment Bond for 100% of the contract amount and a one year maintenance bond for the full amount of the contract. Bond shall also guarantee payment of the applicable Prevailing Wage Rate per job classification as contained herein. Contractor shall provide verification of Commercial General Liability and Commercial Vehicle Insurance coverage in the minimum amount of $1,000,000 for each occurrence. Worker's Compensation Insurance shall be carried in the amount specified by the Contractor's insurance carrier. The City of Savannah shall be named as "Other Insured" on all policies. Insurance certificate must be submitted with the Performance & Payment Bond.

ASPHALT: Asphalt shall be comprised of new materials and shall be finish course grade for overlays. Overlay material shall be Type C Mix Asphalt concrete with an MC-60-70 or AC 20 penetration.

PREVAILING WAGE RATES: The current, applicable wage rate schedule issued by the Missouri Department of Labor is contained herein. Contractor is responsible for paying each employee working on the job, no less than the amounts specified for each job classification present on the job. Contractor is responsible for submitting weekly payrolls to document the wage and benefits paid to each employee.

E-VERIFY: Contractor must E-verify all employees, and provide verification that employees working on-site have received the required ten hour OSHA training as mandated by the State of Missouri. The successful bidder must present verifications for E-verify and OSHA training with their executed contract.

WORKMANSHIP: In general, all work shall meet or exceed AWPA requirements for asphalt paving and milling.

- The work site must be kept in a clean and neat manner.
- Contractor shall manually cut around manholes (or their concrete blocking), storm water inlets and similar obstacles and remove loose debris to insure that the new asphalt shall have a uniform and tight seal around such infrastructure protrusions.
- A tack coat shall be applied immediately prior to the overlay being installed. When swept, the residue shall be contained and removed from the work site. Sweeping shall not blow materials into yards, driveways or streets.
- Overlay material shall be Type C Mix Asphalt Concrete with an MC-60-70 or AC 20 penetration.
- Overlay shall be laid and compacted to provide a continuous, smooth surface between curbs and/or street edges, and from the starting to finish points for each individual section.
- Joints between new overlay and existing asphalt shall be milled or cut cleanly, overlaid and compacted so as to provide a smooth transition without dips or humps.
- Contractor is responsible for all traffic control during the project.
- Joints with intersecting streets not in the project shall be made at the intersection of ROW lines, unless it is necessary to extend the milling/overlay work farther down a non-project street to obtain a smooth transition.

Bid Form

Bids are due April 2, 2015 at 10:00 a.m. local time. Bids will be received at Savannah City Hall, 402 Court, Savannah, MO 64485. Facsimile and email bids will not be accepted. All bids must be sealed and labeled **"Savannah 2015 Asphalt Streets".**

William Street from 8th to 10th, 2" mill and 2" overlay $_____
(Footage 651' x 22')

Davis Street from 8th to 10th, 2" mill and 2" overlay $ _____
(Footage 651' x 21')

Benton Street from 3rd to 5th, 2" mill and 2" overlay $ _____
(Footage 835' x 24'

Benton Street from 5th to 6th, 2" mill and 2" overlay $ _____
(Footage 371' x 22')

2nd Street from Price to Dead End, 2" overlay $ _____
(Footage 547' x 22')

16th Street from Chestnut to W. Main Terr, 2" overlay $ _____
(Footage 791' x 21')

Arbor Street from Andrew Street to Bus. Hwy. 71, 2" overlay $ _____
(Footage 2,010' x 24')

Cedar Street from E Hwy to Price , 2" overlay $ _____
(Footage 1,950' x 24')

TOTAL $_____

All streets should be field verified by the bidder.

Contractor's Name: _____

Address: _____

_____

Phone: _____ Fax: _____ Email: _____

Authorized Signature: _____

Printed Name & Title: _____